

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20117-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 21-14S-10W
3081 feet from S Section Line, 2316 feet from E Section Line
Lease Name: VOPAT D Well #: 1
County: ELLSWORTH Total Vertical Depth: 2918 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2788		
SURF	8.625	276		175 SXS CMT
PROD	4.5	2918		450 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/28/2011 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: SEE BELOW. NO PERFS OR MENTION OF CASING LEAK OR CIBP ON CP-1. OBTAINED THAT INFO FROM RICHARD MCINTYRE.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/28/2011 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU-HAD PRESSURE--HAD TO BLEED OFF INTO TANK TRUCK. RUN TUBING TO TOP OF CIBP--PULL UP 30-40' AND SPOT 25 SX'S CEMENT. PULL TUBING OUT AND PERFORATE AT 1200', 900', AND 325'. RUN TUBING BACK DOWN TO 1200' AND PUMP 35 SX'S CEMENT WITH 3% CC AND 100 #'S COTTON HULLS. PULL TUBING TO 900' AND PUMP 35 SX'S CEMENT WITH 3% CC AND 100#'S COTTON HULLS. PULL TUBING UP TO 325' AND LET CEMENT SET UP. RUN WIRELINE DOWN AND TAG CEMENT TOP AT 393'. CIRCULATE 40 SX'S CEMENT FROM 325' TO SURFACE. PULL TUBING OUT AND TOP OFF. CONNECTED ON TO SURFACE CASING AND PUMPED 95 SX'S--PRESSURED UP TO 150#'S AND SHUT-IN. TOPPED OFF CASING AGAIN WITH 10 MORE SX'S.

Perfs:

Top	Bot	Thru	Comments
2838	2850	CSG	

Remarks: 60-40 POZ, 4% GEL. PIONEER WIRELINE #33310. QUALITY TICKET #5186. COMPLIANCE OVER 10 YEARS INACTIVE.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED

MAY 17 2011

KCC WICHITA