

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20331-00-00
Spot: SENESE Sec/Twnshp/Rge: 28-21S-2W
1654 feet from S Section Line, 326 feet from E Section Line
Lease Name: STUCKY C Well #: 1
County: MCPHERSON Total Vertical Depth: 3384 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	0	0		NO INFO ON WELL
PROD	4.5	3325	813	250 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/18/2011 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 04/21/2011 1:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

4/18/11 KELSO'S DROPPED SAND. KELSO'S TAGGED SAND @ 2938' AND CAPPED W/4 SX. THEY RIPPED CASING @ 813'. THEY PULLED CASING AND LAID IT DOWN. RIGGED DOWN AND MOVED OFF. COPELAND BE OUT WITH POLY TRAILER AND DO TOP PLUG. 4/19/11 COPELAND OUT RAN POLY TO 400' AND CIRCULATED CEMENT TO SURFACE. LOST CIRCULATION. TK #37666 275 SX 60/40 POS W/4% GEL. 4/20/11 I CHECKED TOP PLUG DOWN 250' PLUS. 4/21/11 COPELAND OUT AND RAN POLY DOWN AND TAGGED @ 280' THEY CIRCULATED CEMENT TO SURFACE. TK #37668 140 SX 60/40 POS W/4% GEL. 4/22/11 TOP PLUG AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
3038	3049	CSG	

RECEIVED
MAY 19 2011
KCC WICHITA

Remarks: WELL DONE OVER 10 YEARS DENIED TA

Plugged through: TBG

District: 02

Signed 

(TECHNICIAN)

JK