

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19424-00-00
Spot: NWSENE Sec/Twnshp/Rge: 1-30S-5E
3672 feet from S Section Line, 1214 feet from E Section Line
Lease Name: BROWN UNIT Well #: 8
County: COWLEY Total Vertical Depth: 2830 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	125		75 sxs
PROD	5.5	2803		80 sxs

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/29/2011 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: JOE BURNETT Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 03/29/2011 12:15 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

1-3-2011, RIH W/TBG & BIT, DRILLED CEMENT FROM 687'-747'. 1-5-2011, GRESSEL OILFIELD SERVICE RIH W/WIRELINE SHOT SQUEEZE HOLES @ 700' & 250'. 3-29-2011, RIH W/TBG @ 707' GRESSEL OILFIELD MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL AND DISPLACED IN CASING. PULLED TBG @ 250', GRESSEL OILFIELD SERVICES MIXED & PUMPED 165 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 12:15 PM, 3-29-2011. GRESSEL CEMENTING TICKET #37637.

Perfs:

Top	Bot	Thru	Comments
2803	2830	OH	

RECEIVED
MAY 19 2011
KCC WICHITA

Remarks: ABANDONED WELL, ORIGINAL DOCKETED WELL FOR LEASE/PLUGGED DUE TO COMPLIANCE

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)