

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21240-00-00
Spot: W2SENESE Sec/Twnshp/Rge: 6-16S-10W
1650 feet from S Section Line, 430 feet from E Section Line
Lease Name: KK Well #: 1
County: ELLSWORTH Total Vertical Depth: 3400 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO., A GEN
Address: 140 W WICHITA AVE
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	237		160 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/19/2010 6:00 PM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: _____ Company: ROYAL DRILLING, INC. Phone: _____

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: B. J. HOPE Witness Type: NONE
Date/Time Plugging Completed: 04/19/2010 8:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

PUMP 35 SX'S THRU DP @ 3298', PULL TO 1350' & PUMP 35 SX'S, PULL TO 1050' & PUMP 35 SX'S, PULL TO 287' & PUMP 35 SX'S, PULL TO 60' & PUMP 25 SX'S TO SURFACE. 15 SX'S IN RAT HOLE, 10 SX'S IN MOUSE HOLE. USED 190 SX'S TOTAL.

Remarks: 60-40 POZ, 4% GEL. QUALITY CEMENT TICKET #3810.

Plugged through: DP

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

KCC WICHITA

RECEIVED
MAY 17 2011

JK