

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19207-00-00  
Spot: NWSWNWNE      Sec/Twnshp/Rge: 9-27S-6E  
4301 feet from S Section Line,      2334 feet from E Section Line  
Lease Name: MCGINNIS      Well #: 7  
County: BUTLER      Total Vertical Depth: 2796 feet

Operator License No.: 6407  
Op Name: FLOWERS PRODUCTION CO., INC.  
Address: PO BOX 249  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	12.5	1058		
PROD	6.625	2758		

Well Type: OIL      UIC Docket No:      Date/Time to Plug: 04/02/2011 8:00 AM  
Plug Co. License No.: 32701      Plug Co. Name: C & G DRILLING, INC.  
Proposal Rcvd. from: DALLAS FLOWERS      Company: FLOWERS PRODUCTION      Phone: (316) 321-0550

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER      Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/08/2011 5:00 PM      KCC Agent: DUANE KRUEGER

Actual Plugging Report:

4-2-2011, TAG BOTTOM @ 2776', FLUID LEVEL @ 600'. DUMP 45 GAL GRAVEL. 4-4-2011, TAG BOTTOM @ 2755' DUMP 90 GAL SAND. TAG BOTTOM @ 2700', DUMP BAILED 7 SXS CEMENT ON TOP. 4-5-2011, LOADED HOLE TO SURFACE & SHOT SQUEEZE HOLES FROM 250'-251'. 4-8-2011, SWEDGED INTO 5-1/2" CASING & ESTABLISHED CIRCULATION, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 337 SXS 60/40 POZMIX 4% GEL, 1% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 4-8-2011, 5:00 PM. CONSOLIDATED CEMENT TICKET #30858.

Perfs:

Top	Bot	Thru	Comments
2758	2796	OH	

RECEIVED  
MAY 19 2011  
KCC WICHITA

Remarks: 10 YEAR TA

Plugged through: TBG

District: 02

Signed

Duane Krueger  
(TECHNICIAN)