

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19208-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 9-27S-6E
5026 feet from S Section Line, 2222 feet from E Section Line
Lease Name: MCGINNIS Well #: 11
County: BUTLER Total Vertical Depth: 3146 feet

Operator License No.: 6407
Op Name: FLOWERS PRODUCTION CO., INC.
Address: PO BOX 249
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	5.5	3129		
PROD 7		2765		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/30/2011 8:00 AM
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.
Proposal Rcvd. from: DALLAS FLOWERS Company: FLOWERS PRODUCTION CO., INC. Phone: (316) 321-0550

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 04/08/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

3-30-2011, TAG BOTTOM @ 3138', FLUID LEVEL @ 1125'. DUMP 10 GAL GRAVEL & 60 GAL SAND. 4-2-2011, DUMP BAILED 5 SXS CEMENT ON TOP @ 3075', LOADED HOLE TO SURFACE & SHOT SQUEEZE HOLES FROM 250'-251'. 4-8-2011, SWEDGED INTO 5-1/2" CASING & ESTABLISHED CIRCULATION, CONSOLIDATED OILWELL SERVICES MIXED & PUMPED 387 SXS 60/40 POZMIX 4% GEL, 1% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 4-8-2011, 5:00 PM. CONSOLIDATED CEMENT TICKET #30859.

Perfs:

Top	Bot	Thru	Comments
3129	3146	OH	OPEN HOLE

RECEIVED
MAY 19 2011
KCC WICHITA

Remarks: 10 YEAR TA

Plugged through: TBG

District: 02

Signed _____

Duane Krueger
(TECHNICIAN)