

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19209-00-00  
Spot: NENENE Sec/Twnshp/Rge: 9-27S-6E  
4986 feet from S Section Line, 564 feet from E Section Line  
Lease Name: MCGINNIS Well #: 12  
County: BUTLER Total Vertical Depth: 3137 feet

Operator License No.: 6407  
Op Name: FLOWERS PRODUCTION CO., INC.  
Address: PO BOX 249  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.25	80		
PROD	5.5	3125		20 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/06/2011 8:00 AM  
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.  
Proposal Rcvd. from: DALLAS FLOWERS Company: FLOWERS PRODUCTION CO., INC. Phone: (316) 321-0550

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/11/2011 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:  
4-6-2011, TAG BOTTOM @ 3105', FLUID LEVEL @ 800', DUMP 30 GAL SAND. 4-7-2011, TAG BOTTOM @ 3070', DUMP BAILED 5 SXS CEMENT ON TOP @ 3070'. 4-11-2011, LOADED HOLE TO SURFACE & SHOT SQUEEZE HOLES FROM 260'-261'. 4-11-2011, SWEDGED INTO 5-1/2" CASING & ESTABLISHED CIRCULATION, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 270 SXS 60/40 POZMIX 4% GEL , 1% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 4-11-2011, 5:00 PM. CONSOLIDATED CEMENT TICKET #30973.

Perfs:

Top	Bot	Thru	Comments
3125	3133	OH	OPEN HOLE

RECEIVED  
MAY 19 2011  
KCC WICHITA

Remarks: 10 YEAR TA  
Plugged through: TBG

District: 02 Signed Duane Krueger  
(TECHNICIAN)

JK