

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 34318  
Name: Berexco, L.L.C.  
Address 1: P. O. Box 723  
Address 2: P. O. Box 20380, Wichita, KS 67206  
City: Hays State: KS Zip: 67601 +  
Contact Person: Robert Grant  
Phone: ( 785 ) 628-6101  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: Injection  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: E11512.2  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
LKC A Depth to Top: 3115 Bottom: 18 T.D. \_\_\_\_\_  
LKC D Depth to Top: 3156 Bottom: 58 T.D. \_\_\_\_\_  
LKC G Depth to Top: 3192 Bottom: 99 T.D. \_\_\_\_\_

API No. 15 - 15-009-20943-00-01  
Spot Description: \_\_\_\_\_  
N2 SW NW Sec. 30 Twp. 18 S. R. 11  East  West  
3,530 3462 Feet from  North /  South Line of Section  
4,020 4597 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Barton  
Lease Name: Bailey Unit Well #: T-1 W-8 WIW  
Date Well Completed: 9-15-75  
The plugging proposal was approved on: 9-27-10 (Date)  
by: Pat Staab (KCC District Agent's Name)  
Plugging Commenced: 9-29-10  
Plugging Completed: 9-29-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8	212	none
		Production	5 1/2	3419	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf 2 holes 200', 675' and 1050'. Run tubing to 3020', spot 100 sx 60/40 4% gel and 250# hulls. Pull to 2001', spot 100 sx 60/40 4% gel and 150# hulls. Pull to 1024' spot 60 sx 60/40 4% gel and 100# hulls, circ to surface. Pull tubing, hook to 5 1/2, pump 5 sx 60/40 4% gel. Press to 500#, hold 5/8 full of cement.

RECEIVED  
OCT 04 2010

KCC WICHITA

Plugging Contractor License #: 34318 Name: Berexco, L.L.C.  
Address 1: P. O. Box 723 Address 2: 2020 N. Bramblewood, Wichita, KS 67206  
City: Hays State: KS Zip: 67601 +  
Phone: ( 785 ) 628-6101  
Name of Party Responsible for Plugging Fees: Berexco, L.L.C.  
State of Kansas County, Sedgwick, ss.  
Robert Grant  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Robert Grant