

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4

March 2009

Type or Print on this Form

Form must be Signed

All blanks must be Filled

OPERATOR: License #: 4787
Name: TDI, Inc.
Address 1: 1310 Bison Road
Address 2:
City: Hays State: KS Zip: 67601
Contact Person: Tom Denning
Phone: (785) 628-2593
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
Water Supply Well Other: SWD Permit #:
ENHR Permit #: Gas Storage Permit #:
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Depth to Top: Bottom: T.D.
Depth to Top: Bottom: T.D.
Depth to Top: Bottom: T.D.

API No. 15 - 051-26098-00-00
Spot Description:
SE NW NE NW Sec. 20 Twp. 14 S. R. 16 East West
500 Feet from North / South Line of Section
1,680 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
NE NW SE SW
County: Ellis
Lease Name: Baier Well #: 1
Date Well Completed: 4/27/2011
The plugging proposal was approved on: 4/26/2011 (Date)
by: Ray Dinkel (KCC District Agent's Name)
Plugging Commenced: 4/27/2011
Plugging Completed: 4/27/2011

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Row 1: Surface, 8 5/8", 235.74', 0'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Well was plugged with 215 sacks 60/40 Poz, 4% gel, 1/4# flo-seal per sack, 1st plug @ 3380' with 25 sacks, 2nd plug @ 1042' with 25 sacks, 3rd plug @ 406' with 70 sacks, 4th plug @ 286' with 40 sacks, 5th plug @ 40' to surface with 10 sacks, 15 sacks for mouse hole, 30 sacks for rat hole, plug was down @ 10:00 am on 4/27/2011, by Quality (Ticket #4421).

RECEIVED

MAY 02 2011

Plugging Contractor License #: 33350 Name: Southwind Drilling, Inc.
Address 1: PO Box 276 Address 2:
City: Ellinwood State: Kansas Zip: 67526
Phone: (620) 564-3800

KCC WICHITA

Name of Party Responsible for Plugging Fees: TDI, Inc.
State of Kansas County, Barton, ss.
Jennifer Heape (Print Name) Employee of Operator or Operator on above-described well.

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Jennifer Heape

SOUTHWIND DRILLING, INC.
PLUGGING ORDERS AND REPORTS

Lease: Baier #1

Plugging received from KCC representative:

Name: Ray Dinkel Date 4-26-11 Time 8:30 AM

1st plug @ 3380 ft. 25 sx. Stands: 53 1/2

~~2nd plug @ 1042 ft. 25 sx. Stands: 16 1/2~~

3rd plug @ 406 ft. 70 sx. Stands: 6 1/2

4th plug @ 286 ft. 40 sx. Stands: 4 1/2

5th plug @ 40 ft. 10 sx. Stands: _____

Mousehole 15 sx.

Rahole 30 sx.

Total Cement used: 215 sx.

Type of cement 60/40 POZ, 4% Gel, 1/4 #Flt Seal Per Sack

Plug down @ 10:00 AM 4-27-11

Call KCC-When Completed: _____

Name: Bruce Basye Date 4-28-11 Time 11:00 AM

RECEIVED
MAY 02 2011
KCC WICHITA