

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 31786
Name: OCFIW Oil Company, Inc.
Address 1: P.O. Box 756
Address 2: _____
City: Hartington, State: NE Zip: 68733
Contact Person: Rob Howell
Phone: (402) 254-6585
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No

API No. 15 - 113-20,722-00-00
Spot Description: NW NW SW
Sec. 5 Twp. 21 S. R. 5 East West
2302 2110 Feet from North / South Line of Section
330 5051 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: McPherson
Lease Name: Lackey Well #: A-2
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: Virgil Clothier (KCC District Agent's Name)

Producing Formation(s): List All (If needed attach another sheet)
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

Plugging Commenced: 10-20-10
Plugging Completed: 10-21-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8-5/8"	216'	None
			4-1/2"	3402'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 3300' and 4 sacks cement. Perforated casing @800', 400' & 260'. Ran 2-3/8" tubing to 800', pumped 35 sacks cement, pulled up to 400', pumped 35 sacks cement, pulled up to 260' and circulated 85 sacks cement to surface. Topped off with 20 sacks. Used 60/40 pos, 4% gel. Plugging Complete.

RECEIVED

NOV 04 2010

Plugging Contractor License #: 31529 Name: Mike's Testing & Salvage, Inc. **KCC WICHITA**

Address 1: P.O. Box 467 Address 2: _____

City: Chase State: Kansas Zip: 67524 + 0467

Phone: (620) 938-2943

Name of Party Responsible for Plugging Fees: OCFIW Oil Company, Inc.

State of Kansas County, Rice, ss.

Mike Kelso Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mike Kelso