

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 33699  
Name: T-N-T ENGINEERING, INC  
Address 1: 9250 COSTILLA AVE STE 510  
Address 2: \_\_\_\_\_  
City: ENGLEWOOD State: CO Zip: 80112 + \_\_\_\_\_  
Contact Person: DAVID GIBBONS  
Phone: (303) 253-7831  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
L-KC Depth to Top: 3016' Bottom: 3080' T.D. 3083'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 167-08,553-00-00  
Spot Description: SE/4  
SW SW SE \_\_\_\_\_ Sec. 9 Twp. 15 S. R. 13  East  West  
328 Feet from  North /  South Line of Section  
2,091 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: RUSSELL  
Lease Name: ROESNER Well #: 10  
Date Well Completed: JUNE 1940  
The plugging proposal was approved on: 10-05-2010 (Date)  
by: CASE MORRIS (KCC District Agent's Name)  
Plugging Commenced: 10-06-2010  
Plugging Completed: 10-06-2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		SURFACE	10-3/4"	616'	0
		PRODUCTION	7"	3053'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1ST PLUG @ 2804'; 16 SX GEL FOLLOWED W/ 75 SX CEMENT W/ 200# HULLS. PULLED TBG TO 1500', 2ND PLUG ; 100 SX CEMENT W/ 200# HULLS. PULLED TBG TO 850', 3RD PLUG; 130 SX CEMENT W/ 200# HULLS & CEMENT TO SURFACE. TOH W/ TBG, PUMP 10 SX CEMENT VIA CSG. PUMPED VIA 10-3/4" SURFACE W/ 5 SX CEMENT W/ CEMENT OUT 7" CSG. TOTAL CEMENT 320 SX 60/40 POZ 4% GEL & 600# HULLS.

Plugging Contractor License #: 31925 Name: QUALITY WELL SCV  
Address 1: 190 US 56 HWY Address 2: \_\_\_\_\_  
City: ELLINWOOD State: KS Zip: 67530 + \_\_\_\_\_  
Phone: (620) 938-2388  
Name of Party Responsible for Plugging Fees: T-N-T ENGINEERING, INC  
State of KANSAS County, RUSSELL, ss.  
RICKEY POPP  Agent  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.  
Signature: Rickey Popp

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
OCT 29 2010  
KCC WICHITA