

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 32446  
Name: Merit Energy Company  
Address 1: 13727 Noel Rd., Suite 500  
Address 2: \_\_\_\_\_  
City: Dallas State: TX Zip: 75240 + \_\_\_\_\_  
Contact Person: Lynne Moon/Regulatory Manager  
Phone: (972)-628-1569

Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)  
Morrow Depth to Top: 5642' Bottom: 5719' T.D. 6000'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 189-21531000-00  
Spot Description: WCSWNW Sec. 20 Twp. 31 S. R. 38  East  West  
2240-3095 Feet from \_\_\_\_\_  South Line of Section  
550-4736 Feet from  East \_\_\_\_\_ Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW

County: Stevens  
Lease Name: Spikes "A" Well #: 4 A  
Date Well Completed: 12/2/92  
The plugging proposal was approved on: 9/16/10 (Date)  
by: Steve Pfifer (KCC District Agent's Name)  
Plugging Commenced: 10/19/10  
Plugging Completed: 10/22/10

RECEIVED  
10-28-10  
OCT 28 2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	1717'	NONE
		Production	5 1/2"	5893'	1789'

KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tbg set 5 1/2" 10K CIBP & set @ 5600', circulate hole w/ mud & cap w/ 5 sks cement. Cut 5 1/2" at 1789' & POH w/ 5 1/2" csg. TIH w/ tbg @ 1767', mix & spot 80 sks Class "C" cement up to 1472', pull up hole w/ tbg @ 600' & spot 50 sks Class "C" cement up to 416', did not circulate, SD & WOC overnight, Tag TOC @ 753', run tbg @ 600' & spot additional 50 sks Class "C" cement up to 416', POH w/ tbg & top out 64' - 4' w/ 15 sks Class "C" cement.

DR

Plugging Contractor License #: 33338 Name: ORR ENTERPRISES, INC.  
Address 1: P.O. Box 1706 Address 2: \_\_\_\_\_  
City: Duncan State: Oklahoma Zip: 73534 + 1706  
Phone: (580) 467-0258

Name of Party Responsible for Plugging Fees: Merit Energy Company  
State of Texas County: Dallas ss. \_\_\_\_\_  
Cindy Chavez  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature]