

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5145  
Name: Dreiling Oil, Inc.  
Address 1: P.O. Box 550  
Address 2: \_\_\_\_\_  
City: Hays State: Ks. Zip: 67601 + \_\_\_\_\_  
Contact Person: Terry W. Piesker  
Phone: (785) 625-8327  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: D-13,898  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 15-051-20121-0000  
Spot Description: \_\_\_\_\_  
NW SW NE Sec. 15 Twp. 13 S. R. 19  East  West  
3,633 Feet from  North /  South Line of Section  
2,395 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ellis  
Lease Name: Dreiling Well #: 3-SWD  
Date Well Completed: 9-18-67  
The plugging proposal was approved on: 9-26-10 (Date)  
by: Pat Staab (KCC District Agent's Name)  
Plugging Commenced: 10-01-10  
Plugging Completed: 10-07-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Arbuckle	Water	Surface	8 5/8"	160'	
		Long String	4 1/2"	3750'	
			D.V Tool- 1370'	With 400 sxs.	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

10-01-10 Ran Work String in to 3495'- Mixed 100 sxs 60/40 Poz with 4% Gel and 300# Hulls. Circulation almost immediately. Pulled up to 2200' and mixed 75 sxs. 60/40 Poz 4% Gel with 200# Hulls. Pulled to 1000' and mixed 80 sxs. 60/40 Poz, 4% Gel and cement circulated. Pulled Tubing and tied to 4 1/2" Casing and mixed 5 sxs. 60/40 Poz 4% Gel and pressured to 400#. SIP- 400#. Backside had Hanger. Dug out backside and welded with 2" Nipple coming off 8 5/8" Casing.  
10-07-10 Tied to 8 5/8" and pumped 3/4 Bbl. water and pressured to 200#. SIP- 200#. Job complete.

Plugging Contractor License #: 99977 Name: Quality Oilwell Cementing, Inc.  
Address 1: P.O. Box 31 Address 2: \_\_\_\_\_  
City: Russell State: Kansas Zip: 67665 + \_\_\_\_\_  
Phone: (785) 483-2025  
Name of Party Responsible for Plugging Fees: Dreiling Oil, Inc.  
State of Kansas County, Ellis, ss. Terry W. Piesker  
Terry W. Piesker (Print Name)  Employee of Operator or  Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Terry W. Piesker

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
OCT 28 2010  
10-28-10  
KCC WICHITA

DR  
KCC