

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5003
 Name: McCoy Petroleum Corporation
 Address 1: 8080 E. Central Ave.
 Address 2: Suite #300
 City: Wichita State: KS Zip: 67206-2366
 Contact Person: Scott Hampel
 Phone: 316-636-2737

Type of Well (Check One): Oil Well Gas Well O&G D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
None Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number 15-065-23664 0000
 Spot Description: NW NE NW Sec 33 Twp 10 S. Rng. 25 East West
330 Feet from North / South Line of Section
1650 Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: Graham
 Lease Name: RIEDEL "A" #1-33
 Date Well Completed: 7/25/10
 The plugging proposal was approved on: 7/25/10 (Date)
 by: Ray Qinkel (KCC District Agent's Name)
 Plugging Commenced: 7/25/10
 Plugging Completed: 7/25/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	215' KB	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

7/25/10: Quality plugged hole with 220 sx 60/40 pozmix with 4% gel and 1/4#/sk floseal as follows: heavy mud in hole to bottom plug, 25 sx @ 2140', 100 sx @ 1208', 40 sx @ 265', 10 sx @ 0-40', 30 sx in rathole and 15 sx in mousehole. Plugging completed at 3:15 A.M.. Orders from Ray Qinkel, KCC.

Plugging Contractor License #: 5142 Name: Sterling Drilling Company
 Address 1: P.O. Box 1006 Address 2: _____
 City: Pratt State: KS Zip: 67124-9509
 Phone: 620-672-9508

Name of Party Responsible for Plugging Fees: McCoy Petroleum Corporation
 State of Kansas County, Sedgwick, ss.

Scott Hampel (Vice President - Production) Employee of Operator or Operator on above-described well,
 being first duly sworn on oath, says: that I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Scott Hampel

RECEIVED
OCT 26 2010

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC WICHITA