

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 3602 Name: Philpott Oil & Gas Co., Inc. Address 1: 408 Main Address 2: P.O. Box 450 City: Atwood State: KS Zip: 67730 + 0450 Contact Person: Roger W. Philpott Phone: (785) 626-3011 (785) 626-4006 cell Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: SWD Permit #: D-19,424 ENHR Permit #: Gas Storage Permit #: Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (if needed attach another sheet) Depth to Top: Bottom: T.D.

API No. 15 - 153-00015-0002 Spot Description: C-SW-SW-SW Sec. 33 Twp. 1 S. R. 32 East West Feet from 330 332 Feet from 300 4987 Feet from East / West Line of Section Footages Calculated from Nearest Outside Section Corner: NE NW SE SW County: Rawlins Lease Name: J. W. Kompus "A" Well #: 4 SWD Date Well Completed: August 12, 1978 The plugging proposal was approved on: October 1, 2010 (Date) by: Case Morris, KCC District #4 (KCC District Agent's Name) Plugging Commenced: October 13, 2010 2:30 PM Plugging Completed: October 13, 2010 3:30 PM

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Rows include 2210' to 2260' White Sand/Saltwater Surface 8 5/8" 407' None and 2314' to 2696' White Sand/Saltwater Producing 4 1/2" 2777' None.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hooked up to 4 1/2" casing, pumped 200 sks 60/40 poz w/4% gel mixed w/600# cottonseed hulls down casing till casing full and pressured to 450#; then pumped 25 sks 60/40 poz w/4% gel to fill backside; hooked back up to 4 1/2" casing to start pumping, casing still standing full @ 450#. Cleaned up and moved off location.

Cut off & removed 8 5/8" surface pipe and 4 1/2" casing 9' below surface level. Refilled cellar with dirt and restored & graded location surface to original contour.

RECEIVED OCT 25 2010

Plugging Contractor License #: 3152 Name: Poe Servicing, Inc. Address 1: P.O. Box 115 Address 2: City: Oberlin State: KS Zip: 67749 + 0115 Phone: (785) 475-3422

KCC WICHITA

DR

Name of Party Responsible for Plugging Fees: Philpott Oil & Gas Co., Inc. State of Kansas County, Rawlins, ss. Roger W. Philpott (Print Name) Employee of Operator or Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Roger W. Philpott