

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 30458  
Name: RJM Oil Company, Inc.  
Address 1: P.O. Box 256  
Address 2: \_\_\_\_\_  
City: Clafin State: KS Zip: 67525 + 0256  
Contact Person: Chris Hoffman  
Phone: ( 620 ) 786-8744  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 009-25413-00-00  
Spot Description: \_\_\_\_\_  
SW SW SE Sec. 31 Twp. 18 S. R. 11  East  West  
330 Feet from  North /  South Line of Section  
2,310 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Barton  
Lease Name: Kimpler Well #: 1  
Date Well Completed: 06/04/2010  
The plugging proposal was approved on: 10/14/2010 (Date)  
by: Bruce Bayse (KCC District Agent's Name)  
Plugging Commenced: 10/15/2010  
Plugging Completed: 10/18/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	265'	0'
		Production	5-1/2"	3464'	1488'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

10/15/10 - Drove to location. Tailgate safety meeting. Rig up. Sanded well. Set up jacks. Tagged sand @ 3100'. Pulled slips. Did stretch 5-1/2". Bailed 5 sacks of cement. Cleaned tools. Shut down.

10/18/10 - Drove to location. Tailgate safety meeting. Rigged up perforators. Cut off casing @ 1488'. Pulled casing to 1400'. Dumped 140 sacks of cement. Pulled to 600'. Dumped 25 sacks of cement. Pulled to 300'. Circulated to surface w/135 sacks of cement. Pulled the rest of casing. Total jts of casing pulled - 36. Loaded up jacks. Broke well head. Cleaned tools. Rigged down. Went to next location.

Plugging Contractor License #: 6901 Name: D.S. & W. Well Servicing, Inc.  
Address 1: 1822 24th Street Address 2: \_\_\_\_\_  
City: Great Bend State: Kansas Zip: 67530 + \_\_\_\_\_  
Phone: ( 620 ) 793-5838  
Name of Party Responsible for Plugging Fees: RJM Oil Company, Inc.  
State of Kansas County, Barton, ss.  
Tim Dickson  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Tim Dickson

RECEIVED

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

OCT 25 2010

KCC WICHITA