

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 05721
Name: Glacier Petroleum, Inc.
Address 1: P.O. Box 577
Address 2: _____
City: Emporia State: KS Zip: 66801 + 0577
Contact Person: J.C. Hawes
Phone: (620) 342-1148
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: E-23863 Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Viola Depth to Top: 2942 Bottom: 2943 T.D. 2943
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 127-19006-00-00
Spot Description: _____
NE NE NE Sec. 23 Twp. 16 S. R. 9 East West
4,976 Feet from North / South Line of Section
397 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Morris
Lease Name: Viar Well #: #1
Date Well Completed: 3.14.1957
The plugging proposal was approved on: 11.15.2010 (Date)
by: Shana Jones (KCC District Agent's Name)
Plugging Commenced: 11.16.2010
Plugging Completed: 11.16.2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			10 3/4"	132 ft	0
			7"	2942 ft	0
			4 1/2"	2917 ft	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Wireline plug set at 2800 ft., Cement circ from 289 ft inside 4 1/2" to surface (10 3/4, 7" and 4 1/2" all cemented to surface)

Consolidated Tk# 29987

RECEIVED
NOV 23 2010
11-23-10
KCC WICHITA

DR

Plugging Contractor License #: 05721 Name: Glacier Petroleum, Inc.
Address 1: P.O. Box 577 Address 2: _____
City: Emporia State: KS Zip: 66801 + 0577
Phone: (620) 342-1148
Name of Party Responsible for Plugging Fees: Glacier Petroleum, Inc.
State of Kansas County: Lyon, ss. _____
J. C. Hawes Employee of Operator or Operator on above-described well;
(Print Name)

being first duly sworn on oath, says That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY	
11-16-10	3314	VIAR SWD #1	23	16S	9E	MORRIS	
CUSTOMER GLACIER Petroleum, Inc.			Safety Meeting Km				
MAILING ADDRESS P.O. Box 577							
CITY EMPORIA		STATE KS	ZIP CODE 66801	TRUCK #	DRIVER	TRUCK #	DRIVER
				445	SHANNON		
				479	ALLEN B.		

JOB TYPE P.T.A. HOLE SIZE _____ HOLE DEPTH _____ CASING SIZE & WEIGHT 4 1/2
 CASING DEPTH _____ DRILL PIPE _____ TUBING 2 3/8 OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety Meeting: RAN 2 3/8 Tubing to 289'. Rig up to 2 3/8. Spot Solid Cement Plug From 289' to SURFACE inside 4 1/2 casing. PULL 2 3/8 Tubing. Top of casing w/ Cement. Total Cement used to Plug = 30 sks 60/40 Pozmix w/ 4% Gel. Job Complete. Rig down.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405 A	1	PUMP CHARGE	625.00	625.00
5406	70	MILEAGE	3.65	255.50
1131	30 SKS	60/40 Pozmix Cement	11.35	340.50
1118 B	100 *	Gel 4%	.20	20.00
5407	1.29 TONS	Ton Mileage Bulk Delv.	M/C	315.00
				RECEIVED
				NOV 23 2010
				KCC WICHITA
			Sub Total	1556.00
			SALES TAX 7.3%	26.32
			ESTIMATED TOTAL	1582.32

AUTHORIZATION By Jeff Hawes TITLE President DATE _____
 THANK YOU 238018