

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 6407  
Name: Flowers Production Co., Inc.  
Address 1: P.O. Box 249  
Address 2: \_\_\_\_\_  
City: El Dorado State: KS Zip: 67042 + \_\_\_\_\_  
Contact Person: Dallas Flowers  
Phone: (316) 321-0550  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Mississippi Depth to Top: 2678 Bottom: 2727 T.D. 2727  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 015-21868<sup>1</sup> 0600  
Spot Description: \_\_\_\_\_  
NE SW NW SE Sec. 1 Twp. 25 S. R. 3  East  West  
1,689 Feet from  North /  South Line of Section  
2,313 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Butler  
Lease Name: Moore C Well #: 5  
Date Well Completed: 9-23-81  
The plugging proposal was approved on: 3-16-10 (Date)  
by: Duane Krueger (KCC District Agent's Name)  
Plugging Commenced: 3-16-10  
Plugging Completed: 3-16-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Mississippi	oil & water	surface	8 5/8"	200+	none
	2678-2727	production	4 1/2"	2726	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIH W/TBG CIRCULATING HOLE CLEAN @ 2270, DRILLING ON IRON, LAYED TBG DOWN, SDFN. RAN MAGNET, PULLED LOTS OF METAL PIECES BACK OUT OF HOLE. RIH W/TBG @ 2270', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 40 SXS 60/40 POZMIX 4%GEL, 3% CC DISPLACED IN CSG. TAGGED CEMENT @ 1838'. PRESSURED WELL, WOULD NOT HOLD. PUMPED FLAG, HOLE @ 1606'. RIH W/TBG @ 1587', CONSOLIDATED MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL, 3%CC AND DISPLACED IN CSG. TAGGED CEMENT @1486'. PRESSURED CSG, HELD OK. SHOT SQUEEZE HOLES @271-272', SWEDGED INTO 4 1/2" CSG, CONSOLIDATED MIXED & PUMPED 118 SXS 60/40 POZMIX 4%GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM, 3-16-10. CEMENT TICKET #23315. 3-18-10, RIH W/STRING LINE ON BACKSIDE OF CSG @175', DID NOT TAG CEMENT. 6-4-10, CONSOLIDATED TAGGED CEMENT INSIDE 4 1/2" CSG @90', AND OUTSIDE 4 1/2" CSG @180'. NO FLUIDS IN HOLE, CONSOLIDATED MIXED & PUMPED 65 SXS 70/30 POZMIX 2%GEL TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED CEMENT TICKET #28475. P.A. COMPLETE 6-4-10.

Plugging Contractor License #: 5870 Name: Phillips Well Service, Inc.  
Address 1: P.O. Box 1263 Address 2: \_\_\_\_\_  
City: El Dorado State: KS Zip: 67042 + \_\_\_\_\_  
Phone: (316) 321-6650  
Name of Party Responsible for Plugging Fees: Flowers Production Co., Inc.  
State of Kansas County, Butler, ss.  
Dallas Flowers  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: 

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
NOV 30 2010  
KCC WICHITA

**BILL JOHNSON**  
Petroleum Geologist  
STAR STREET VENTURES

COPY

Phone  
316-321-1270 Office  
316-321-4709 Home

September 21, 1981

MAILING ADDRESS  
1015 Douglas Rd  
EL DORADO, KANSAS 67042

Mary Spivey  
% R. J. Wixson Drilling Co.  
P.O. Box 18153  
Wichita, Kansas 67218

Re: Moore "C" 5

~~SW-NW-SE~~

Section 1-T25S-R3E

Butler County, Kansas

Dear Mary,

The following report on the subject well is based on microscopic examination of rotary drill cuttings from 2100 feet to rotary total depth of 2727 feet. All measurements were taken from Kelly bushing which was five feet above ground level.

The following tops were picked:

Elevation of Kelly bushing	1315	Estimated
Kansas City	2230	(- 915)
Base Kansas City	2398	(-1083)
Marmaton	2464	(-1149)
Cherokee	2604	(-1289)
Conglomerate	2632	(-1317)
Mississippi	2678	(-1363)
RTD	2727	(-1412)

MAJOR ZONES OF INTEREST

Kansas City. 2286-2299. Limestone, light tan, fine to coarse crystalline, good crystalline porosity, no shows.

2338-2352. Limestone, light tan, fine to coarse crystalline, fair to good crystalline porosity, no shows.

RECEIVED

NOV 30 2010

KCC WICHITA

Page 2

Moore "C" 5  
SW NW SE  
Section 1-T25S-R3E  
Butler County, Kansas

Mississippi. 2690-2697. Dolomite, calcareous, light tan, chalky, medium crystalline, fair crystalline porosity, weak odor, weak show free oil, fluorescence 15%.

2699-2705. Dolomite, tan, sucrosic, medium crystalline, fair odor, friable fragments, weak show free gassy oil, fluorescence 20%.

2710-2724. Dolomite, light tan, fine to medium crystalline, fair crystalline porosity, no shows.

SUMMARY

Due to oil shows in Mississippi  $4\frac{1}{2}$  inch casing was run and cemented to test the Mississippi for production.

Sincerely yours,



Bill Johnson

nj

RECEIVED  
NOV 30 2010  
KCC WICHITA