

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 3942
Name: Big O LLC
Address 1: 2820 Paseo Drive
Address 2: _____
City: Great Bend, State: Ks. Zip: 67530
Contact Person: Orville Monroe
Phone: (620) 793-2134
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 145-21358-0000
Spot Description: C-SW-NW-SE
Sec. 24 Twp. 20 S. R. 16 East West
1650 1692 Feet from North South Line of Section
2310 2335 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Pawnee
Lease Name: NBA Well #: 1-24
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: Richard Lacey (KCC District Agent's Name)
Plugging Commenced: 9-28-10
Plugging Completed: 9-30-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		<u>surf.</u>	8-5/8"	1101	None
			5-1/2"	3933'	2100'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 3750' and 5 sacks cement. Cut casing loose @2100'. pulled up to 1140', pumped 15 sacks gel and 50 sacks cement., pulled up to 450', pumped 50 sacks cement, pulled up to 40', and circulated 20 sacks cement to surface. Used 60/40 pos, 4% gel. Plugging complete.

Plugging Contractor License #: 31529 Name: Mike's Testing & Salvage, Inc.
Address 1: P.O. Box 467 Address 2: 1125 Main
City: Chase, State: Kansas Zip: 67524 + 0467
Phone: (620) 938-2943
Name of Party Responsible for Plugging Fees: Big O, LLC
State of Kansas County, Rice, ss.
Mike Kelso Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Mike Kelso

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
OCT 13 2010
KCC WICHITA