

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4058
Name: American Warrior INC
Address 1: P.O.Box 399
Address 2: _____
City: Garden City State: KS Zip: 67846 + _____
Contact Person: Kevin Wiles SR
Phone: (620) 275-2963
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Kansas City Depth to Top: 2921 Bottom: 2930 T.D. 3272
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

Handwritten initials

API No. 15- 159-02162-00 00
Spot Description: NE SW SE NW NW 18-19s-9w
SE-SE-NW Sec. 18 Twp. 19 S. R. 9 East West
2,981 Feet from North / South Line of Section
3,407 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Rice
Lease Name: Kate Well #: 1
Date Well Completed: 7-22-1941
The plugging proposal was approved on: 9-24-10 (Date)
by: Virgil Clothier (KCC District Agent's Name)
Plugging Commenced: 9-27-10
Plugging Completed: 9-27-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	259	None
		Production	5-1/2"	3268	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIPB @ 2870', Dump 2 sks cement on plug, perf 4- holes @ 1200', 850', & 310', Ran 2-3/8" tbg, to 1200', pump 50sks common cement, pull tbg to 850' pump 50 sks common cement, pull tbg to 310' circulate cement w/ 100 sks 60/40 poz 4% gel, pull tbg, top off casing, Job complete

Handwritten initials AR

RECEIVED

OCT 19 2010

Plugging Contractor License #: 99996 Name: Allied Cementing Co.
Address 1: P.O.Box 31, Address 2: _____
City: Russell State: KS Zip: 67665 + _____
Phone: (785) 483-2627
Name of Party Responsible for Plugging Fees: American Warrior INC
State of Kansas County, Barber ss. _____
Kevin Wiles SR Employee of Operator or Operator on above-described well,
(Print Name)

KCC WICHITA

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____