

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 31191  
Name: R & B Oil & Gas, Inc  
Address 1: 124 N. Main  
Address 2: P.O. Box 195  
City: Attica State: KS Zip: 67009 + 9217  
Contact Person: Randy Newberry  
Phone: (620) 254-7251  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Miss. Depth to Top: 4291 Bottom: 4330 T.D. 4500  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

API No. 15 - 095-22160-0000  
Spot Description: NE SE SW  
NE SE SW Sec. 20 Twp. 30 S. R. 8  East  West  
990 Feet from  North /  South Line of Section  
2,970 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Kingman  
Lease Name: Carrick Well #: 1  
Date Well Completed: 8-12-2008  
The plugging proposal was approved on: 4-19-2010 (Date)  
by: Jeff Klock (KCC District Agent's Name)  
Plugging Commenced: 7/19/10  
Plugging Completed: 7/21/10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	270	195 Sacks Cement
Miss	Gas	Production	5 1/2	4494	165 Sacks Cement

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand @ 4230'. Bailed 5 sacks cement on sand. Cut surface off 4' below ground. Ripped casing at 3510' & 3320'; pipe came free. Pulled casing up to 1350' & pumped 35 sacks 3%cc & 100# hulls. Pulled to 850' & pumped 35 sacks 3 %cc & 100 #hulls. Pulled to 320 & pumped 135 sacks to surface. Topped well off with 25 sacks, dry.

RECEIVED

OCT 08 2010

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc. **KCC WICHITA**  
Address 1: 190 US Highway 56 Address 2: \_\_\_\_\_  
City: Ellinwood State: KS Zip: 67526 + \_\_\_\_\_  
Phone: (620) 727-3410

Name of Party Responsible for Plugging Fees: R & B Oil & Gas, Inc.  
State of Kansas County, Harper, ss.  
Randy Newberry (Print Name)  Employee of Operator or  Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Randy Newberry

# QUALITY WELL SERVICE, INC.

5015

Home Office 190th US 56 HWY, Ellinwood, KS 67526

Todd's Cell 620-388-5422  
Darin's Cell 785-445-2686

Rich's Cell 620-727-3409  
Brady's Cell 620-727-6964

Date	7-21-10	Sec.	20	Twp.	30	Range	8	County	Kern	State	Ks	On Location		Finish	
Lease	CARRICK	Well No.	1	Location		SPUR Ks E to Mag Plant BK?									
Contractor QWS								Owner 25 1/2 W N into							
Type Job PTA								To Quality Well Service, Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.							
Hole Size 7 7/8				T.D.				Charge To R & B O.L. & EAS. TAC							
Csg. 5 1/2				Depth 1350				Street							
Tbg. Size				Depth				City				State			
Tool				Depth				City				State			
Cement Left in Csg.				Shoe Joint				The above was done to satisfaction and supervision of owner agent or contractor.							
Meas Line				Displace				Cement Amount Ordered							
EQUIPMENT								215 60/40 Poz 49% ECL							
Pumptrk	6	No.	TOON				Common								
Bulktrk	2	No.	KEUIN				Poz. Mix								
Bulktrk		No.					Gel.								
Pickup		No.					Calcium 2								
JOB SERVICES & REMARKS								Hulls 200'							
Rat Hole								Salt							
Mouse Hole								Flowseal							
Centralizers								Kol-Seal							
Baskets								Mud CLR 48							
D/V or Port Collar								CFL-117. or CD110 CAF 38							
7-21-10								Sand							
1st Plug 1350'								Handling 229							
355x 60/40 Poz w/ 1/2 cc 100" hulls								Mileage 53							
Disp H <sub>2</sub> O								FLOAT EQUIPMENT							
								Guide Shoe							
2nd Plug 350'								Centralizer							
355x 60/40 Poz w/ 1/2 cc 100" hulls								Baskets							
Disp H <sub>2</sub> O								AFU Inserts							
								Float Shoe							
3rd Plug 320'								Latch Down							
120x 60/40 Poz															
TRC Cam to Pit															
								Pumptrk Charge PTA							
7-22-10 25 SW TOP OFF								Mileage 53							
thanks															
Todd Quality															
Signature								Tax							
								Discount							
								Total Charge							

RECEIVED  
OCT 08 2010  
KCC WICHITA

PLEASE  
CALL  
MAM