

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 30204 32426  
Name: H & L OPERATING CO., LLP  
Address 1: P.O. BOX 7506  
Address 2: \_\_\_\_\_  
City: AMARILLO State: TX Zip: 79114 + 7506  
Contact Person: RONALD P. MOON  
Phone: ( 806 ) 353-4331  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
COUNCIL GROVE Depth to Top: 2917 Bottom: 2922 T.D. 6449  
MORROW Depth to Top: 5705 Bottom: 5715 T.D. \_\_\_\_\_  
ST. LOUIS Depth to Top: 6196 Bottom: 6202 T.D. \_\_\_\_\_

API No. 15 - 119-20826 -00-02  
Spot Description: \_\_\_\_\_  
SE SE SE Sec. 16 Twp. 35 S. R. 30  East  West  
330 Feet from  North /  South Line of Section  
330 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: MEADE  
Lease Name: ADAMS RANCH Well #: 1-16  
Date Well Completed: 04/03/1991  
The plugging proposal was approved on: 06/10/2010 (Date)  
by: JERRY STAPLETON (KCC District Agent's Name)  
Plugging Commenced: 06/11/2010  
Plugging Completed: 06/15/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
COUNCIL GROVE	GAS/WATER	0-1464	8 5/8	1464	0
MORROW	GAS/CONDENSATE	0-6449	4 1/2	6449	1510
ST. LOUIS	GAS	0-6449	4 1/2	6449	1510

RECEIVED  
DEC 27 2010  
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 40 bbl mud down 4-1/2" csg. TIH w/ bridge plug and set at 2850'. Pumped 10 sxs cement. Shot 4-1/2" csg at 1510'. Layed down 34 joints of csg. TIH with tubing to 1530'. Pumped two sxs cotton seed hulls with mud. Pumped 75 sxs cement. TOH to 600'. Pumped 50 sxs cement. TOH to 62'. Pumped 15 sxs cement

Plugging Contractor License #: 33311 Name: PHIL DOLLAR OILFIELD SERVICES, INC.  
Address 1: P.O. BOX 744 Address 2: \_\_\_\_\_  
City: PERRYTON State: TX Zip: 79070 + 0744  
Phone: ( 806 ) 435-3373

Name of Party Responsible for Plugging Fees: H & L OPERATING CO., L.L.P.  
State of TEXAS County, RANDALL, ss.  
RONALD P. MOON  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Ronald P. Moon