

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30705
Name: Younger Energy Company
Address 1: 453 S. Webb Road, Suite 100
Address 2: _____
City: Wichita State: KS Zip: 67207 + 1310
Contact Person: Diane Rebstock
Phone: (316) 681-2542
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No C-10 If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3345 Bottom: 3370 T.D. 3370

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 009-21,265; 60 00
Spot Description: 100' S of C NW NE NW

Sec. 3 Twp. 18 S. R. 13 East West
4850 Feet from North / South Line of Section
3630 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barton
Lease Name: Morrison Ludwig Well #: 1
Date Well Completed: 2/7/1978
The plugging proposal was approved on: 2-28-11 (Date)
by: Bruce Rodie (KCC District Agent's Name)
Plugging Commenced: 2/28/2011
Plugging Completed: 2/28/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	495'	none
		Production	5-1/2"	3358'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Existing perforations at 3345'-3351' and bridge plugs previously set at 3210', 3288', and 3354'. Ran tools in & perforated squeeze holes - 2 shots @ 450' and 2 shots @ 775'. Ran in with tubing and tagged bridge plug at 3210'. Pumped 13 sxs gel, 1 sx hulls, and 50 sxs cement at 3210', displaced with 10 bbls freshwater. Pumped 75 sxs cement and 1 sx hulls @ 1410', displaced with 2 bbls freshwater. Pumped 68 sxs cement @ 775', circulated to surface. Pumped 70 sxs cement down casing. Used total of 263 sxs.60/40 Pozmix, 4% gel.

Plugging Contractor License #: 34044 Name: JD's Well Service, Inc.
Address 1: P.O. Box 542 Address 2: _____
City: Clafin State: KS Zip: 67525 + _____
Phone: (620) 588-2345
Name of Party Responsible for Plugging Fees: Younger Energy Company, 453 S. Webb Rd., Suite 100, Wichita, KS 67207
State of Kansas County, Sedgwick, ss.
Diane Rebstock Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Diane Rebstock, V.P. Finance

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
APR 25 2011
KCC WICHITA