

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34506
Name: EMPIRE ENERGY E&P, LLC
Address 1: 17 ARENTZEN BLVD, SUITE 203
Address 2: _____
City: CHARLEROI State: PA Zip: 15002 + _____
Contact Person: KIM HOFFMAN
Phone: (620) 786-1720
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
ARBUCKLE Depth to Top: 3591' Bottom: 3594' T.D. 3594'
~~L-KC Depth to Top: 3376' Bottom: 3434' T.D. 3594'~~
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 185-13092-00-01
Spot Description: NE/4
S/2 NW NE Sec. 20 Twp. 21 S. R. 12 East West
4,290 Feet from North / South Line of Section
1,980 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: STAFFORD
Lease Name: F SYMS Well #: 1
Date Well Completed: 12-42
The plugging proposal was approved on: 4-18-11 (Date)
by: RICHARD LACEY (KCC District Agent's Name)
Plugging Commenced: 4-20-11
Plugging Completed: 4-20-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		SURFACE	8-5/8"	245'	NONE
		PRODUCTION	5-1/2"	3591'	NONE

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

TIH W/ TBG TO 3538', PUMPED VIA TBG 10 SX GEL FOLLOWED W/ 50 SX CEMENT. PULLED TBG UP TO 700', PUMPED VIA TBG 80 SX CEMENT W/ CEMENT TO SURFACE. TOH W/ TBG, TOPPED OFF CSG W/ 15 SX CEMENT. TOTAL CEMENT USED WAS 145 SX 60/40 POZ 4% GEL.

RECEIVED
APR 25 2011

Plugging Contractor License #: 6123 Name: CHASE WELL SVC, INC
Address 1: PO BOX 355 Address 2: _____
City: GREAT BEND State: KS Zip: 67530 + _____
Phone: (620) 793-9556

KCC WICHITA

Name of Party Responsible for Plugging Fees: EMPIRE ENERGY E & P, LLC
State of KANSAS County, STAFFORD, ss. RICKEY POPP
 Agent of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Rickey Popp