

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5135
Name: John O. Farmer, Inc.
Address 1: P.O. Box 352
Address 2: _____
City: Russell State: KS Zip: 67665 + 0 3 5 2
Contact Person: Marge Schulte
Phone: (785) 483-3145, Ext. 214
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: SWD Permit #: D-18,090
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Cedar Hills Depth to Top: 550' Bottom: 884' T.D. 884'
(SWD Zone) Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - -151-20,294-00 00
Spot Description: _____
NE SW NW Sec. 23 Twp. 29 S. R. 13 East West
1650 3746 Feet from North / South Line of Section
990 4189 Feet from East West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Pratt
Lease Name: Kinzie Well #: SWD
Date Well Completed: August, 1975
The plugging proposal was approved on: prior to plugging (Date)
by: District #1 (KCC District Agent's Name)
Plugging Commenced: 9:00 A.M., 11-16-10
Plugging Completed: 10:00 A.M., 11-16-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
742-772', 730-736'		surface	8-5/8"	200'	-0-
736-750', 712-720'		production	5-1/2"	808'	-0-
550-884' (Cedar Hills)					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hooked up to casing & mixed 200# hulls. Mixed 40 sks. 60/40 Pozmix; shut down; hooked up to backside & mixed 5 sks. cement; shut down; washed.

TOTAL: 45 sks. 60/40 Pozmix, 200# hulls

RECEIVED
DEC 08 2010

KCC WICHITA

Plugging Contractor License #: 99996 Name: Allied Cementing Company, LLC.
Address 1: P.O. Box 31 Address 2: _____
City: Russell State: Kansas Zip: 67665 + 0 0 3 1
Phone: (785) 483-2627
Name of Party Responsible for Plugging Fees: John O. Farmer, Inc.
State of Kansas County, Russell, ss.
John O. Farmer III, President of John O. Farmer, Inc. Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained; and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: John O. Farmer III 12-7-10

KANSAS DRILLERS LOG

S. 23 T. 29 R. 13 ^K/_W


API No. 15 — 151 — 20,294
County Number

COPY

Loc. NE SW NW

County Pratt

640 Acres
N



Locate well correctly

Elev.: Gr. 1898

DF 1901 KB 1903

Operator
John O. Farmer, Inc.

Address
Box 352, 370 West Wichita Ave., Russell, Kansas 67665

Well No. #1 SWD Lease Name Kinzie

Footage Location
990 feet from (N) (S) line 990 feet from (E) (W) line

Principal Contractor Pratt Well Service Geologist _____

Spud Date July 22, 1975 Total Depth 884' P.B.T.D. Open Hole

Date Completed August 5, 1975 Oil Purchaser _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8-5/8	26	200	Common	200	
Long String	7-7/8	5-1/2	10	808	Common	200	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	Jets	550-554
			2	Jets	536-542
			2	Jets	523-528
			2	Jets	793-798

TUBING RECORD

Size	Setting depth	Packer set at
2 1/2	520	520

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1000 gal. 15%	808-884
1500 gal. 15% total on above listed perforations	

RECEIVED
DEC 08 2010

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) KCC WICHITA

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on an open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

John O. Farmer, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

SWD

Well No.

SWD

Lease Name

Kinzie

Rate: 22 BWPB

S 23 T 29 R 13 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Sand & Shale	0	150		
Red Bed	150	780		
Sand & Shale	780	884		

RECEIVED
DEC 08 2010
KCC WICHITA

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

John O. Farmer
Signature
President
Title
August 6, 1975
Date

ALLIED CEMENTING CO., LLC. 042264

REMIT TO: P.O. BOX 31
RUSSELL, KANSAS 67665

COPY

SERVICE POINT:
Medicine Lodge, KS

DATE <u>11-16-2010</u>	SEC. <u>23</u>	TWP. <u>29S</u>	RANGE <u>13W</u>	CALLLED OUT <u>7:00 AM</u>	ON LOCATION <u>9:00 AM</u>	JOB START <u>9:00 AM</u>	JOB FINISH <u>10:00 AM</u>
LEASE <u>67212</u>	WELL # <u>360</u>	LOCATION <u>Sguyer, ks north on Hwy</u>				COUNTRY <u>KS</u>	STATE <u>KS</u>
<input checked="" type="radio"/> OLD		<input type="radio"/> NEW (Circle one)		<u>281 to 90th rd, 1/2 way, 5/16</u>			
CONTRACTOR: <u>John O Farmer</u>				OWNER: <u>John O Farmer</u>			
TYPE OF JOB: <u>Oil Well</u>				CEMENT: <u>POZMIX</u>			
HOLE SIZE: <u>5 1/2</u>				DEPTH: <u>880</u>			
CASING SIZE: <u>5 1/2</u>				AMOUNT ORDERED: <u>455x60 40x49 60</u>			
TUBING SIZE: <u>4 1/2</u>				DEPTH: <u>880</u>			
DRILL PIPE: <u>4 1/2</u>				DEPTH: <u>880</u>			
TOOL JOINT: <u>4 1/2</u>				DEPTH: <u>880</u>			
PRES. MAX: <u>27.5x @ 15.45</u>				MINIMUM: <u>417.15</u>			
MEAS. LINE: <u>POZMIX</u>				SHOE JOINT: <u>8.00 @ 174.00</u>			
CEMENT LEFT IN CSG: <u>2.0x @ 20.80</u>				GEL: <u>47.60</u>			
PERFS: <u>CHLORIDE</u>				ASC: <u>112.80</u>			
DISPLACEMENT: <u>312.00</u>				TOTAL: <u>1027.55</u>			

EQUIPMENT

PUMP TRUCK / CEMENTER: <u>Derrin</u>	CHARGE: <u>101.75</u>
# <u>360-265</u> SHELLER: <u>M9217</u>	CHARGE: <u>7.00</u>
BULK TRUCK # <u>381-290</u> DRIVER: <u>Robert</u>	CHARGE: <u>140.00</u>
BULK TRUCK # <u>47</u>	CHARGE: <u>112.80</u>
HANDLING MILEAGE: <u>49.10/20</u>	CHARGE: <u>312.00</u>
TOTAL: <u>1027.55</u>	

REMARKS:

Hook up to casing 9m may 2004
at Willis may 405x of cement 511
down, hook up to bear side 9m may
55x of cement, shut down, wash up

DEPTH OF JOB 880'

PUMP TRUCK CHARGE 101.75

EXTRA FOOTAGE 7.00

MILEAGE 140.00

MANIFOLD

CHARGE TO: John O Farmer

TOTAL: 1157.00

STREET: _____

CITY: _____ STATE: _____ ZIP: _____

PLUG & FLOAT EQUIPMENT

To Allied Cementing Co., LLC

You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner of contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the GENERAL TERMS AND CONDITIONS listed on the reverse side.

SALES TAX (if Any): None

TOTAL CHARGES: 1157.00

PRINTED NAME: X Val Decker

SIGNATURE: X Val Decker

IF PAID IN 30 DAYS

Thank You!!!

RECEIVED
DEC 08 2010
KCC WICHITA