

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 7030
Name: John Roy Evans Oil Company, LLC
Address 1: P.O. Box 385
Address 2: _____
City: Clafin State: KS Zip: 67525 + 0385
Contact Person: Gary Kirmer
Phone: (620) 793-2026
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
SEE ATTACHED Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 141-20230-0000
Spot Description: _____
NE SW NE Sec. 2 Twp. 10 S. R. 15 East West
3,630 Feet from North / South Line of Section
1,650 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Osborne
Lease Name: Finnessy Well #: 3
Date Well Completed: 1/5/1987
The plugging proposal was approved on: 10/14/2010 (Date)
by: Case Morris (KCC District Agent's Name)
Plugging Commenced: 10/22/2010
Plugging Completed: 10/22/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Topeka 2852-3088	oil/water/gas	surface	8 5/8"	701'	RECEIVED DEC 14 2010 KCC WICHITA
Toronto 3085-3088	oil/gas	production	4 1/2"	3530	
Lansing/KC 3126-3382	oil/water/gas				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Log Tech perf 2 holes @ 1500'; 2 holes @ 1140'; 2 holes @ 690'. Ran 2 3/8" tubing into hole and tagged bottom @ 2888'. Mixed 150 sx 60/40 poz, 4% gel and spotted on bottom 2868'. Pulled tubing to 1497' and mixed 80sx 60/40 poz, 4% gel. Pulled tubing to 683', mixed 80 sx poz, 4% gel and circulated cement to surface. Pulled tubing out, topped off 4 1/2" with 10 sx and topped off 8 5/8" with 10 sx.

DR

Plugging Contractor License #: 6426 Name: Express Well Service & Supply, Inc.
Address 1: P.O. Box 19 Address 2: _____
City: Victoria State: KS Zip: 67671 + 0019
Phone: (785) 735-9405
Name of Party Responsible for Plugging Fees: John Roy Evans Oil Company, LLC
State of Kansas County, Barton, ss.
Gary Kirmer Employee of Operator or Operator on above-described well,
(Print Name)
being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Gary Kirmer

John Roy Evans Oil Company, LLC
P.O. Box 385
Clafin, KS 67525

Well Plugging Record (CP4) Attachment for
Finnesy #3

Producing Formations:

Topeka 2854-2859
 3031-3035

Lansing/KC 3220-3226
 3285-3289
 3301-3302
 3310-3316
 3337-3340

RECEIVED
DEC 14 2010
KCC WICHITA