

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-00020-00-01
Spot: SWSW Sec/Twnshp/Rge: 32-18S-31W
621 feet from S Section Line, 4663 feet from E Section Line
Lease Name: CHRISTY Well #: 1-32
County: SCOTT Total Vertical Depth: 4666 feet

Operator License No.: 33476
Op Name: FIML NATURAL RESOURCES, LLC
Address: 410 17TH ST STE 900
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1610		
CIBP		2700		
SURF	8.625	368		WITH 200 SX CMT
PROD	4.5	2850	0	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/28/2011 10:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: EDDIE ABERCROMBIE Company: FIML Phone: (620) 793-2816

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/28/2011 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG SET CIBP @ 2700'. 2ND PLUG RAN TBG & PACKER TO 1609'. ESTABLISH RATE. PUMPED 85 SX CMT & 50# HULLS. DISPLACE. SHUT IN 450#. 3RD PLUG TOHWT. SET CIBP @ 1610'. PERFORATE AT 1596'. ESTABLISH RATE. PUMP 140 SX CMT. 50 SX CMT OUT PERFS. NO BLOW. 4TH PLUG HOOK UP 8 5/8" X 4 1/2" ANNULUS & PUMP 120 SX CMT. MAXIMUM PRESSURE 100#. SHUT IN PRESSURE 100#.

Perfs:

Top	Bot	Thru	Comments
2782	2784		Krider

RECEIVED
MAY 23 2011

Remarks: USED 60/40 POZMIX 4% GEL & CLASS A COMMON CMT BY CONSOLLIDATED.

KCC WICHITA

Plugged through: CSG

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED
MAY -6 2011
KCC DODGE CITY

Handwritten initials