

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21106-00-00
Spot: SENENE Sec/Twnshp/Rge: 7-12S-17W
4265 feet from S Section Line, 391 feet from E Section Line
Lease Name: HERMAN Well #: 1
County: ELLIS Total Vertical Depth: 3671 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	252	0	130 SX
PROD	5.5	3657	0	75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/16/2011 2:45 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: GRADY BOLDING CORPORATION Phone: (620) 562-0895

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls - 11 sxs gel.
DV Tool at 1352' w/300 sxs.
Lease worked up by Pat Staab.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/16/2011 5:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Mike's Testing and Salvage RIH to 3600'.
Copeland rigged to tubing and pumped 11 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 150# hulls mixed in.
Pulled to 2000'. Copeland rigged to tubing and pumped 100 sxs cement with 250# hulls mixed in.
Pulled tubing to 1000'. Copeland rigged to tubing and pumped 130 sxs cement with 200# hulls to circulate cement to surface.
Pulled tubing - topped off 5 1/2" casing with 30 sxs cement - hole standing full.
Rigged to 8 5/8" - pumped 5 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3657	3671		OPEN HOLE

RECEIVED
MAY 23 2011
KCC WICHITA

Remarks: COPELAND CEMENTING COMPANY-TICKET #36331.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

Form CP-2/3

MAY 19 2011