

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-073-19947-00-00

Spot: NWSWNW

Sec/Twnshp/Rge: 25-25S-8E

1650 feet from N Section Line,

330 feet from W Section Line

Lease Name: JACKSON HEIRS

Well #: 1

County: GREENWOOD

Total Vertical Depth: 2365 feet

Operator License No.: 5697

Op Name: JACKSON BROTHERS, L.L.C.

Address: 116 E 3RD ST  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	130		
PROD	5.5	2336		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/17/2010 8:00 AM

Plug Co. License No.: 6112

Plug Co. Name: LONG DRILLING COMPANY, LLC

Proposal Rcvd. from: ROSCOE G. JACKSON II

Company:

Phone: (620) 583-5122

Proposed Plugging Method: SPOT 20 SACKS CEMENT THROUGH 2-3/8" EUE TUBING AT 2230' FOR BOTTOM PLUG; 30 SACKS THROUGH 2-3/8" AT 1200' FOR MIDDLE PLUG; CONTINUOUS CEMENT PLUG INSIDE 5 1/2" FROM 250' TO G.L. NOTE: OUTSIDE OF 5 1/2" IS CEMENTED FROM 345' TO G.L., AS PER ATTACHED CONSOLIDATED TICKET #29940 DATED 5 NOV. 2010.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed 12/23/2010 12:00 AM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 2335' pumped 30 sxs cement, pulled tubing to 900' pumped 30 sxs cement, pulled tubing to 250' circ. Cement to surface 50 sxs cement. Gel spacers between cement plugs.

RECEIVED

MAY 16 2011 MH

KCC Chanute Dist. #3

RECEIVED

MAY 23 2011

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

M. H. Heffern  
(TECHNICIAN)