

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21976-00-00
Spot: SENWSW Sec/Twnshp/Rge: 8-22S-11W
1686 feet from S Section Line, 4270 feet from E Section Line
Lease Name: HAMMEKE Well #: 2
County: STAFFORD Total Vertical Depth: 3635 feet

Operator License No.: 33964
Op Name: PROLIFIC RESOURCES LLC
Address: 2725 DRY CRK RD
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3310		
CIBP		3580		
SURF	8.626	268		WITH 225 SX CMT
PROD	5.5	3619	1602	WITH 160 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/16/2011 9:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: TIM DICKSON Company: DS & W WELL SERVICING Phone: (316) 269-2015

Proposed Plugging Method: SET CIBP @ 3250' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/16/2011 1:10 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3250' WITH 2 SX CMT ON TOP WITH DUMP BAILER. 1ST PLUG AT 592' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 295' WITH 50 SX CMT. 3RD PLUG AT 42' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3619	3635		ARBUCKLE
3324	3328		LANSING/KC
3283	3286		LANSING/KC

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED
MAY 20 2011
KCC DODGE CITY

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
MAY 24 2011
KCC WICHITA

Form CP-2/3

RWD