

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-20339-00-01
Spot: SWNWNE Sec/Twnshp/Rge: 34-21S-15W
4307 feet from S Section Line, 2369 feet from E Section Line
Lease Name: JOHNSON-SCHARTZ Well #: 1
County: PAWNEE Total Vertical Depth: 3935 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: 453 S WEBB RD STE 100
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	637		
T1	2.375	3867	2544	
PROD	4.5	3925	0	

Well Type: EOR UIC Docket No: E27108.1 Date/Time to Plug: 05/17/2011 8:30 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: LUKE DYCHE Company: YOUNGER ENERGY Phone: (620) 786-4258

Proposed Plugging Method: PUMP DOWN 2 3/8" WITH 30 SX CMT & DISPLACE TO 3600'. FREE POINT & PULL FREE TBG. PERFORATE 4 1/2" @ 960' & CIRCULATE CMT TO SURFACE UP 4 1/2" AND 8 5/8" X 4 1/2" ANNULUS. PULL TBG & TOP OFF HOLE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2011 1:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

2 3/8" TBG & COMPRESSION PACKER STUCK IN HOLE BELOW 2600'. COMPANY MADE MANY ATTEMPTS TO RECOVER. PUMPED 30 SX CMT DOWN THE 2 3/8" & DISPLACED TO 3600'. FREE POINTED TBG @ 2556'. SHOT TBG FREE AT 2544'. PULLED TBG OUT OF HOLE. PERFORATED 4 1/2" @ 960'. RAN TBG BACK IN TO HOLE TO 963'. PUMPED 130 SX CMT DOWN TBG CIRCULATING CMT TO SURFACE UP 4 1/2". SHUT IN 4 1/2" AND PRESSURED IT TO 500 PSIG. NO BLOW ON 8 5/8" X 4 1/2" ANNULUS. PULLED TBG OUT. PUMPED 20 SX CMT DOWN 4 1/2" TO TOP OFF. PRESSURED 8 5/8" X 4 1/2" ANNULUS TO 500 PSIG WITH 2.5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3885	3895		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
MAY 20 2011
KCC DODGE CITY

RECEIVED
MAY 24 2011
KCC WICHITA

Form CP-2/3

Raw