

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20283-00-00
Spot: SEWSE Sec/Twnshp/Rge: 16-30S-9W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: SWINGLE B Well #: 1
County: KINGMAN Total Vertical Depth: 4344 feet

Operator License No.: 32433
Op Name: ONSHORE, L.L.C.
Address: 11126 W. 21ST N.
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	4275		
SURF	8.625	259		
PROD	4.328	6	2800	

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/21/2011 9:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: _____ Company: ONSHORE LLC Phone: (316) 262-3413

Proposed Plugging Method: 50 SXS AT 1300', 50 SX AT 850', CIRCULATRE CEMENT 310' TO SURFACE, CEMENT: 60X40 NO MORE THAN 4% GEL

Plugging Proposal Received By: PATRICK SHIELDS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/21/2011 10:30 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

A CAST-IRON BRIDGE PLUG WAS PLACED AT 4275' W/ 2 SX ON TOP. CASING WAS SHOT OFF AT 1528' AND 2800' WAS RECOVERED FROM HOLE. TUBING WAS LOWERED TO 1300' AND 50 SX WERE SPOTTED. TUBING PULLED TO 850' AND 50 SX WERE ALSO SPOTTED. TUBING WAS THEN RAISED TO 310' AND 100 SX WERE CIRCULATED TO SURFACE. REST OF TUBING PULLED.

Perfs:

Top	Bot	Thru	Comments
4328	4344	OH	

RECEIVED
MAY 25 2011
KCC WICHITA

Remarks: CEMENT 60 X 40 - 4% GEL. QUALITY WELL SERVICE TICKET #5138

Plugged through: TBG

District: 02

Signed [Signature]
(TECHNICIAN)

✓