

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24832-00-00
Spot: SENEENE Sec/Twnshp/Rge: 35-20S-13W
640 feet from N Section Line, 108 feet from E Section Line
Lease Name: HADDON KELLY Well #: 1-35
County: BARTON Total Vertical Depth: 3700 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	288	0	300 SX
T1	2.375	3670		
PROD	5.5	3690	2441	150 SX CMT SMDC FLOCELE

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/23/2011 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: KEVIN WILES, SR Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/23/2011 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perfs and topped with 5 sxs cement.
Cut casing at 2441' - pulled to 1550' and pumped 125 sxs cement with 200# hulls.
Pulled to 700' - pumped 40 sxs cement with 100# hulls.
Pulled to 290' - pumped 40 sxs cement with 100# hulls.
Pulled to 150' - circulated cement to surface with 65 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3600	3604		
3306	3309		
3290	3294		
3284	3287		
3275	3280		
3248	3252		

Remarks: QUALITY WELL SERVICE.

Plugged through: CSG

District: 04

Signed Bruce Rodie

(TECHNICIAN)

RECEIVED
MAY 27 2011
KCC WICHITA
Form CP-2/3
CM

MAY 25 2011