

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-03176-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 1-15S-13W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: FISHER Well #: 1
County: RUSSELL Total Vertical Depth: 2417 feet

Operator License No.: 33633
Op Name: CARTER, JIM DBA J CARTER OIL
Address: PO BOX 491
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	720	720	
COND	10.75	440	440	
PROD	5.5	2413	350	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/17/2011 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JIM CARTER Company: J CARTER OIL Phone: (785)483-8057

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 600# hulls.
Perf: 720'.
10.75" casing and 8.6250" casing was pulled at an earlier date.
Pulled 5.50" casing - 5 1/2" casing parted at 350' when attempting to pull casing.
Tried to run tubing in - could not.
Pulled out and ran a slotted nipple - got into casing and ran to 740' - but got hung up.
Perf thru tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/17/2011 6:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Hooked to tubing and pumped 200 sxs cement with 400# hulls.
Pulled tubing to 330' - pumped 145 sxs cement - cement circulated into cellar.
POOH. Picked one joint of 5 1/2" casing and ran back in - set about three feet below ground level.
05/18/2011 - checked casing and cellar - full.

Remarks: QUALITY WELL SERVICE-TICKET #5191.

Plugged through: CSG

District: 04

Signed

Ray A.O. Kef

(TECHNICIAN)

RECEIVED

MAY 27 2011

KCC WICHITA

CM

Form CP-2/3

MAY 19 2011