

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-04781-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 35-19S-12W  
1650 feet from N Section Line, 990 feet from E Section Line  
Lease Name: JOHANNING Well #: 6  
County: BARTON Total Vertical Depth: 3370 feet

Operator License No.: 31070  
Op Name: EAGLE RIVER ENERGY CORPORATIO  
Address: 7060 S YALE # 702  
TULSA, OK 74136

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| CIBP   |       | 3328       |             |          |
| SURF   | 8.625 | 160        | 0           | 150 SX   |
| PROD   | 5.5   | 3370       | 0           | 175 SX   |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/23/2011 10:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.  
Proposal Rcvd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-2645

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/23/2011 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1200' - 585' - 350'.  
Ran tubing to 3360' - pumped 13 sxs gel - followed with 75 sxs cement with 300# hulls.  
Pulled tubing to 1265' - circulated cement to surface with 120 sxs cement with 200# hulls.  
Pulled tubing - topped off casing with 10 sxs cement.  
Tied to backside and pumped 10 sxs cement.  
Max. P.S.I. 200#.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3367 | 3368 |      |          |
| 3360 | 3367 |      |          |
| 3350 | 3360 |      |          |
| 3338 | 3345 |      |          |
| 3309 | 3313 |      |          |
| 3238 | 3246 |      |          |
| 3223 | 3228 |      |          |
| 3153 | 3157 |      |          |
| 3116 | 3121 |      |          |
| 2902 | 2906 |      |          |

Remarks: COPELAND ACID AND CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

RECEIVED  CM  
MAY 27 2011  
Form CP-2/3  
KCC WICHITA

MAY 25 2011