

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-21090-00-00
Spot: NWNESESW Sec/Twnshp/Rge: 5-35S-12E
1011 feet from S Section Line, 3015 feet from E Section Line
Lease Name: VENAMON Well #: 1
County: CHAUTAUQUA Total Vertical Depth: 1100 feet

Operator License No.: 5451
Op Name: FADELY, DALE LEON
Address: 909 STATE HWY 99
SEDAN, KS 67361

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/27/2010 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: ELMORE'S, INC. Company: _____ Phone: (620) 249-2519

Proposed Plugging Method: 50' plug at TD(1100"), 50' plug at 700' and 350' to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed 12/28/2010 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1100' gelled hole and spotted 10 sack plug. Pulled 1" up to 700' and spotted 5 sack plug. Pulled 1" up to 300' and circulated cement to surface. Pulled 1" and topped well off on inside of 4.5". Ran 1" to 65' on backside of 4.5" and hit cement. Circulated 12 sacks of cement to surface on backside. Pulled 1" and topped off. A total of 57 sacks of cement were used to plug this well.

RECEIVED

MAY 18 2011 DAS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

RECEIVED
MAY 27 2011
KCC WICHITA

Form CP-2/3