

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23717-00-00
Spot: NENESW Sec/Twnshp/Rge: 29-14S-12W
2220 feet from S Section Line, 2310 feet from W Section Line
Lease Name: WILLSON Well #: 2
County: RUSSELL Total Vertical Depth: 3220 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	563		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/13/2011 12:00 PM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: ROBERT STEPHENS Company: JASON OIL COMPANY, LLC Phone: (785) 483-4204

Proposed Plugging Method: Ordered 170 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: NONE
Date/Time Plugging Completed: 05/13/2011 3:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

1st. Plug at 3136' w/25 sxs.
2nd. Plug at 590' w/25 sxs.
3rd. Plug at 350' w/80 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Darrel Dipman
(TECHNICIAN)

RECEIVED
MAY 27 2011
KCC WICHITA
Form CP-2/3
CM

MAY 19 2011