

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-03879-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 14-17S-11W  
4290 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: BLOOMER Well #: 15  
County: BARTON Total Vertical Depth: 3342 feet

Operator License No.: 33186  
Op Name: LB EXPLORATION, INC.  
Address: 2135 2ND RD  
HOLYROOD, KS 67450

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	285	0	w/unknown sxs cmt
PROD	5.5	3321	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/24/2011 12:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: RICKY POPP Company: LB EXPLORATION, INC. Phone: (785) 252-8034

Proposed Plugging Method: Emergency plug with rig over the hole.  
Working on well - could not get down to bottom of well - casing bad at 2300'.  
Decided to plug.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/24/2011 4:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perfed at 1500' - 700' - 250'.  
Ran tubing to 2290' - pumped 150 sxs cement.  
Pulled tubing to 1200' - circulated cement to surface with 115 sxs cement with 600# hulls.  
Pulled tubing - tied to casing - circulated cement to surface on backside with 60 sxs.  
Max. P.S.I. 150#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

RECEIVED CM  
MAY 27 2011 CP-2/3  
KCC WICHITA

MAY 25 2011