

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-20882-00-02
Spot: NESWNW Sec/Twnshp/Rge: 27-33S-12E
3630 feet from S Section Line, 4290 feet from E Section Line
Lease Name: RAYMON E Well #: 6
County: CHAUTAUQUA Total Vertical Depth: 987 feet

Operator License No.: 34103
Op Name: LAMAMCO DRILLING CO., A GENERA
Address: 4444 E. 146TH ST N PO BOX 550
SKIATOOK, OK 74070

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	54		15 SX
PROD	4.5	987		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/01/2010 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: THOMAS H. OAST Company: _____ Phone: (620) 725-3200

Proposed Plugging Method: RUN 2" TUBING TO TD. ESTABLISH CIRCULATION. RUN 10 SACKS GEL. SPOT 100' OF CEMENT. PULL TUBING TO 800'. SPOT 50' OF CEMENT. PULL TUBING TO 350' AND CIRCULATE CEMENT TO SURFACE. RESTORE LOCATION.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 06/16/2010 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 956' gelled hole and spotted 10 sack plug. Pulled 1" up to 700' and spotted 5 sack plug. Pulled 1" up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 50 sacks of cement were used to plug this well. Well was cut off and location restored.

RECEIVED

MAY 18 2011 DAS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

RECEIVED

MAY 27 2011

KCC WICHITA

Form CP-2/3