

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20075-00-00  
Spot: NWNWSE Sec/Twnshp/Rge: 10-15S-15W  
2970 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: BLEHM Well #: 5  
County: RUSSELL Total Vertical Depth: 3310 feet

Operator License No.: 3134  
Op Name: MORRIS, TERRY E. DBA G L M COMPA  
Address: PO BOX 193  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	211	0	w/190 sxs cmt
PROD	5.5	3308	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/12/2011 9:30 AM  
Plug Co. License No.: 34071 Plug Co. Name: PATRIOT WELL SERVICE, INC.  
Proposal Rcvd. from: TERRY MORRIS Company: G L M COMPANY Phone: (785) 483-1307

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Left approximately 2380' of tubing in the hole. Ran wash-over pipe in to 900'.  
Could not recover all tubing. Ran bit on 2 7/8" tubing to 820'.  
Ran 2 3/8" tubing and circulated down to 747'. Hard bottom.  
They were loosing ground every time they tripped out of the well.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/12/2011 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 747' - circulated down to hard bottom.  
Pulled tubing to 720' - pumped 165 sxs cement - cement circulated to surface.  
POOH. Hooked to casing and pumped 40 sxs cement.  
Cement circulated and filled cellar.

Perfs:

Remarks: ALLIED CEMENTING COMPANY-TICKET #39632.

Plugged through: TBG

District: 04

Signed

Ray A. K. D.

(TECHNICIAN)

RECEIVED

MAY 27 2011

KCC WICHITA

Form CP-2/3

MAY 19 2011