

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24378-00-00
Spot: NWSESWNW Sec/Twnshp/Rge: 15-17S-11W
3040 feet from S Section Line, 4360 feet from E Section Line
Lease Name: HERTHEL Well #: 8
County: BARTON Total Vertical Depth: 3370 feet

Operator License No.: 31327
Op Name: PAULEY, GARY DBA PAULEY OIL
Address: 314 5TH ST
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	330	0	w/200 sxs cmt
PROD	5.5	3362	0	w/125 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/19/2011 12:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: GARY PAULEY Company: PAULEY OIL Phone: (785) 252-8024

Proposed Plugging Method: Emergency plug with rig over the hole.
Rig over the hole two weeks - squeezing holes in casing 1050' w/100 sxs; 320' w/225 sxs.
Drilling on cement ran outside of casing at 465'.
Decided to plug.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2011 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Ran tubing to 465' - circulated cement to surface with 60 sxs cement.
Pulled tubing - tied to casing - pumped 10 sxs cement.
Max. P.S.I. 300#. Shut in.
Tied to backside - pressured to 300# P.S.I. - would not take any cement.

Remarks: QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

RECEIVED

MAY 27 2011

CM

KCC WICHITA Form CP-2/3

MAY 23 2011