

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-049-20739-00-00
Spot: Sec/Twnshp/Rge: 4-30S-9E
2970 feet from N Section Line, 990 feet from E Section Line
Lease Name: B W PERKINS Well #: 12
County: ELK Total Vertical Depth: 2393 feet

Operator License No.: 4448
Op Name: PERKINS OIL ENTERPRISES, INC.
Address: PO BOX 707
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	40		15 sxs
PROD	5.5	2393		145 sxs

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/18/2011 8:00 AM
Plug Co. License No.: 34203 Plug Co. Name: PIRATE WELL SERVICE, LLC
Proposal Rcvd. from: J. R. PERKINS Company: _____ Phone: (620) 374-2133

Proposed Plugging Method: Perf casing at 1490' & at 500'. Run tubing to bottom, pump gel & pump 5 sacks cement. Pull tubing to 1490' & pump 5 sacks cement. Pull tubing to 500' & pump cement to surface. Pull rest of tubing and top off.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed 02/18/2011 9:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 2327' gelled hole and spotted 15 sack plug. Pulled up to 1477' and spotted 15 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 2" out of hole. Hooked on and squeezed well. A total of 180 sacks of cement were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
2332	2360		Mississippian

RECEIVED

MAY 18 2011 DAS


KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED
MAY 27 2011

Form CP-2/3

KCC WICHITA