

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-049-20410-00-00

Spot: NENESE

Sec/Twnshp/Rge: 4-30S-9E

2970 feet from N Section Line,

330 feet from E Section Line

Lease Name: PERKINS BARBARA

Well #: 9

County: ELK

Total Vertical Depth: 2362 feet

Operator License No.: 4448

Op Name: PERKINS OIL ENTERPRISES, INC.

Address: PO BOX 707

HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	150		10 sxs
PROD	4.5	2362		75 sxs

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/17/2011 8:00 AM

Plug Co. License No.: 34203

Plug Co. Name: PIRATE WELL SERVICE, LLC

Proposal Rcvd. from: J. R. PERKINS

Company:

Phone: (620) 374-2133

Proposed
Plugging
Method:

Perf at 1490' & 500'. Run tubing to bottom & pump gel & pump 5 sacks cement. Pull tubing to 1490' & pump 5 sacks cement. Pull tubing to 500' pump cement to surface. Pull rest of tubing & top off.

Plugging Proposal Received By: DUANE SIMS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed 02/17/2011 3:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 2" to 2328' gelled hole and spotted 10 sack plug. Pulled 2" up to 1477' and spotted 10 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 2" and topped well off. A total of 140 sacks were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
2314	2342		Mississippian

RECEIVED

MAY 18 2011 DAS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

(TECHNICIAN)

Form CP-2/3

RECEIVED

MAY 27 2011

KCC WICHITA