

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-049-19262-00-00
Spot: SESESE Sec/Twnshp/Rge: 25-30S-10E
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: STEPHENS Well #: 1
County: ELK Total Vertical Depth: 1752 feet

Operator License No.: 4448
Op Name: PERKINS OIL ENTERPRISES, INC.
Address: PO BOX 707
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	42		
PROD	4.54	1616		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/05/2011 12:00 AM
Plug Co. License No.: 34203 Plug Co. Name: PIRATE WELL SERVICE, LLC
Proposal Rcvd. from: KEVIN WARLOW Company: _____ Phone: (620) 330-3666

Proposed Plugging Method: 50' CEMENT PLUG ON BOTTOM GEL TO 1220 10' BELOW PERFS, 50' CEMENT PLUG 1220-1180, GEL TO 350. CEMENT 350 TO SURFACE.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed 01/05/2011 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 2" to 1600' gelled hole and spotted 5 sack plug. Pulled 2" up to 1200' and spotted 5 sack plug. Pulled up to 350' tried to get circulation and couldn't. Middle plug fell back. Ran 2" back into 1000' spotted 5 more sacks with hulls this time. Pulled up to 350' and circulated cement to surface. A total of 55 sacks of cement were used to plug this well.

RECEIVED
MAY 18 2011 DAS
KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed 
(TECHNICIAN)

RECEIVED Form CP-2/3
MAY 27 2011
KCC WICHITA