

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23151-00-00
Spot: SENESW Sec/Twnshp/Rge: 19-15S-13W
1650 feet from S Section Line, 2310 feet from W Section Line
Lease Name: BOOMHOWER Well #: 1
County: RUSSELL Total Vertical Depth: 3405 feet

Operator License No.: 32325
Op Name: POPP OPERATING, INC.
Address: 191 NE 150 RD PO BOX 187
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3270		
SURF	8.625	855	0	325 SX
PROD	5.5	3404	2230	145 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/19/2011 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICKEY POPP Company: POPP OPERATING, INC. Phone: (620) 653-2737

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Cut casing at 2230' - leaving 1174' of 5 1/2" casing - CIBP at 3270'.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2011 2:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

05/18/2011 - Sanded off bottom with 5 sxs cement on top.
05/19/2011 - Cut casing at 2230'.
Pulled casing to 1410' - pumped 125 sxs cement with 400# hulls.
Pulled casing to 800' - pumped 40 sxs cement.
Pulled casing to 450' - pumped 75 sxs cement - cement circulated.
POOH. Topped off hole and cellar with 25 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3304	3306		ARBUCKLE
3056	3234		L-KC
3029	3034		DOUGLAS
2996	3000		TORONTO
2915	2928		PLATTSMOUTH
2749	2878		TOPEKA

Remarks: QUALITY WELL SERVICES-TICKET #5193.

Plugged through: CSG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

RECEIVED

MAY 27 2011 Form CP-2/3

KCC WICHITA

MAY 23 2011