

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-019-19745-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 33-33S-11E  
2836 feet from S Section Line, 1403 feet from E Section Line  
Lease Name: GRIFFITH Well #: 10  
County: CHAUTAUQUA Total Vertical Depth: 150 feet

Operator License No.: 33157  
Op Name: R. D. ENERGY, INC.  
Address: 905 N MONTGOMERY  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.5	0		
PROD	2	0		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/30/2010 10:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: Wash to TD inside and outside production casing and cement bottom to top.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed 06/30/2010 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Well was partially plugged by previous operator. No information on this other than new operator was their to witness. Operator washed down inside of 2" to 150' and hit cement. Washed down on outside of 2" to 90' and hit cement. Operator turned on 1" and drilled up cement both inside and outside of 2". Operator circulated cement to surface inside and outside of 2". Pulled 1" and topped well off. A total of 23 sacks of cement were used to plug this well.

RECEIVED

MAY 18 2011 DAS

KCC Chanute Dist. #3

Remarks: WELL WAS PARTIALLY PLUGGED BY PREVIOUS OPERATOR. NO RECORDS FILED.

Plugged through: TBG

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)

Form CP-2/3

RECEIVED

MAY 27 2011

KCC WICHITA