

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-019-19279-00-01
Spot: SESENE SW Sec/Twnshp/Rge: 3-32S-12E
1561 feet from S Section Line, 2912 feet from E Section Line
Lease Name: LONGTON STORAGE Well #: 43A
County: CHAUTAUQUA Total Vertical Depth: 750 feet

Operator License No.: 33344
Op Name: QUEST CHEROKEE, LLC
Address: OKLAHOMA TOWER 210 PARK AVE,
OKLAHOMA CITY, OK 73102

Well Type: GWI UIC Docket No: _____ Date/Time to Plug: 07/15/2010 8:00 AM
Plug Co. License No.: 33344 Plug Co. Name: QUEST CHEROKEE, LLC
Proposal Rcvd. from: ERNIE GONZALEZ Company: _____ Phone: (405) 600-7704

Proposed Plugging Method: Perforate at 350' and 150'. Cement bottom to top.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed 07/15/2010 5:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perforated well at 350' and 150'. Ran 1" to 750' inside 4.5" and circulated cement to surface. Pulled 1" and ran 1" down backside of 4.5" to 175' and circulated cement to surface. Pulled 1" and topped well off inside and outside of 4.5". A total of 97 sacks of cement were used to plug this well.

Perfs:

RECEIVED

MAY 18 2011 DAS

KCC Chanute Dist. #3

Remarks: KCC IS MAKING OPERATOR PLUG OUT STORAGE FIELD.

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

Form CP-2/3

RECEIVED ✓

MAY 27 2011

KCC WICHITA