


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Logan County, Sec. 2 Twp. 13S Rge. 33WE/W  
Location as "NE/CNW1/4SW1/4" or footage from lines  
C NE NE  
Lease Owner Beren Corporation  
Lease Name VOTH #1 Well No. 1  
Office Address 970 Fourth Financial Center, Wichita KS  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed July 11 19 79  
Application for plugging filed (verbally) July 11 19 79  
Application for plugging approved (verbally) July 11 19 79  
Plugging commenced July 11 19 79  
Plugging completed July 11 19 79  
Reason for abandonment of well or producing formation  
No commercial quantity of oil or gas encountered  
If a producing well is abandoned, date of last production  
19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4750'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

T.D. 4750'  
Set 1st plug at 1350' with 70 sacks  
2nd plug at 360' with 20 sacks  
3rd plug at 40' solid bridge with 10 sacks  
rathole with 3 sacks  
Cemented with 50/50 posmix, 6% gel.  
Plug was down at 11:00 a.m., 7-11-79

RECEIVED  
STATE CORPORATION COMMISSION  
07-17-1979  
JUL 17 1979

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc. CONSERVATION DIVISION  
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of  
the facts, statements, and matters herein contained and the log of the above-described well  
as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge  
801 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of July, 19 79.



Sherrie L. Brooks  
Sherrie L. Brooks Notary Public.

My commission expires 8-21-82

CONTRACTOR'S WELL LOG

OPERATOR: Beren Corporation  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: VOTH #1  
 LOCATION: C NE NE, Section 2-13S-33W  
 Logan County, Kansas  
 SPUD DATE: June 30, 1979  
 COMPLETION DATE: July 11, 1979

0	42	Surface soil
42	372	Clay, sand and shale
372	1380	Shale and sand
1380	1832	Shale with sand
1832	2292	Shale and sand
2292	2550	Lime and shale
2550	2572	Anhydrite
2572	2790	Shale and sand
2790	3052	Shale
3052	3320	Lime and shale
3320	3600	Shale and lime
3600	3908	Lime and shale
3908	3965	Lime with shale
3965	4750	Lime
	4750	Rotary Total Depth

Spud hole at 4:00 p.m., June 30, 1979. Drilled 372' of 12 1/4" hole. Ran 9 joints of used 8-5/8" - 24# casing. Set at 371' R.B. with 250 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Plug was down at 10:30 p.m., June 30, 1979

T.D. 4750'. Set 1st plug at 1350' with 70 sacks, 2nd plug at 360' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks, rathole with 3 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 11:00 a.m., July 11, 1979.

SAMPLE TOPS:

Anhydrite 2550'  
 B/Anhydrite 2572'

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 17 1979  
 07-17-1979  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the VOTH #1, C NE NE, Section 2-13S-33W, Logan County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 16th day of July, 1979.



Sherrie L. Brooks  
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.