

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Logan County. Sec. 21 Twp. 13 Rge. 33 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner E. K. Carey Drilling Co., Inc.

Lease Name Burkhead Well No. 1

Office Address Box 620, McPherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 20, 19 52

Application for plugging filed November 20, 19 52

Application for plugging approved November 20, 19 52

Plugging commenced November 20, 19 52

Plugging completed November 20, 19 52

Reason for abandonment of well or producing formation No commercial showing of oil or gas

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. R. Petty, Box 326, Hays, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4651 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
(Unknown) Sand	Water	80	110	8-5/8	160'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Gunned pits and circulated heavy mud on bottom and half way out, placed 15 sacks cement plug bottomed at 150' with permission from Mr. Petty the top of the hole was left open (requested by the land owner) for the purpose of making a fresh water well by perforation at approximately 100'.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Wykoff & Williams Drilling Company
Address Box 170, Grinnell, Kansas

STATE OF Kansas, COUNTY OF McPherson, ss.
Herbert Rhoton, Supt. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Herbert Rhoton Supt.
Box 620, McPherson, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of November, 19 52

My commission expires November 13, 1956

[Signature]
Notary Public.



PLUGGING
FILE SEC 21 T 13 R 33
BOOK PAGE 62 LINE 42

RECEIVED
STATE CORPORATION COMMISSION
DEC - 2 1952
12-02-1952
CONSERVATION DIVISION
Wichita, Kansas

15-109-00022-00-00

DRILLERS WELL LOG

November 20, 1952

Company The E. K. Carey Drilling Co., Inc.

Sec. 21 Twp. 13S Rge. 33W

Farm Burkhead

Well No. 1 NE NE NE

Total Depth Rotary 4651

County Logan

Comm. 11/2/52 Comp. 11/20/52

State Kansas

Shot or Treated None

Contractor Wycoff-Williams Drilling Co.

Casing: 8 5/8"
160' Cemented

Elevation 2925 K.B.

Production Dry

Figures Indicated Bottom of Formations

Surface Soil & Clay	0-65	Shale & Shells	2960
Sand & Gravel	130	Lime & Shale	2970
Shale	1135	Lime	2977
Shale & Shells & Sand	1470	Lime & Shale	3250
Sand & Shale	1700	Lime	3285
Shale & Shells	1760	Lime & Sand	3340
Sand	1810	Lime & Shale	3810
Red bed & Shale	2020	Lime	3850
Anhydrite	2030	Lime	3885
Shale & Lime	2140	Lime	4220
Shale & Red Bed	2281	Shale	4233
Shale & Lime	2700	Lime	4651
Shale	2900	Total Depth	4651

RECEIVED
12-02-1952

PLUGGINS
FILE SEC 21 T 13 R 33W
BOOK PAGE 42 LINE 42

15-109-00022-00-00

Page #2
Drillers Well Log
NE NE NE 21-13-33
Logan County, Kansas
Burkhead #1

STATE OF Kansas, COUNTY OF Gove, ss.

Wesley E. Williams, (partner) Wycoff-Williams Drilling Co. Contractor of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wesley E. Williams
Box 170, Grinnell, Kans.
(Address)

SUSCRIBED AND SWORN TO before me this 29th day of November, 1952

Harley L. Mc Guinness
Notary Public

My commission expires June 13, 1956



15-109-00022-00-00