

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-109-20,284-

LEASE NAME Garvey "AS"

WELL NUMBER #1

SPOT LOCATION SE SE NE

SEC. 9 TWP. 13 RGE. 33 (E) or (W)

COUNTY Logan

Date Well Completed _____

Plugging Commenced 3-4-86

Plugging Completed 3-10-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Inc.

ADDRESS Box 1447, Great Bend, Ks. 67530

PHONE (316-793-8968) OPERATORS LICENSE NO. 5238

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Six (6)

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing formation _____ Depth to top _____ bottom _____ T.D. 4670'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1331'	None
				5-1/2"	4669'	2,057.72'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Dumped sand to 4100' and 5 sacks cement. Shot casing at 3200', 2500' and 2000'. Pulled 51 joints of 5-1/2" casing. B.J. Titan squeezed well with 3 sacks hulls 23 sacks gel, 100 sacks cement, 1 sack hulls, 17 sacks gel, released plug and pumped 80 sacks 60/40 pozmix cement with 6% added gel and 3% calcium chloride. Maximum pressure was 1500 psi and shutin 500 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 12th day of March, 1986

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
STATE CORPORATION COMMISSION
Notary Public

My Commission expires: _____

MAR 13 1986
03-13-1986
CONSERVATION DIVISION

Form CP-4
Revised 11/85